

▪ **C E S S N A**

**Cessna 441 - Vortex Generator Kit**

**New Operational Weight 10,415 lbs.**

Phase I & II Kits	Factory	BLR modified	Improvement
Gross Ramp Weight	9,925	10,415	+490 lbs.
Gross Takeoff Weight	9,850	10,340	+490 lbs.
Zero Fuel Weight	8,500	8,815	+315 lbs.
Landing Weight	9,360	9,600	+240 lbs.
Vmc	91	91 KIAS	No Change
Stall Speed - Flaps Up	89	91 KIAS	+2
Stall Speed - Flaps Full	77	76 KIAS	+1

**Notes:**

- Speeds listed in Knots, Weights listed in Pounds
- Stall speeds are Certified at NEW Gross Weight, Forward CG and Zero Thrust
- Vmc is certified at light weight, aft CG and the critical engine "wind milling"
- Kit installation time is approximately 8 man-hours

